

“B”

Recommended Conditions of Approval and Final Agency Approval Memos

RECOMMENDED CONDITIONS OF APPROVAL

**Meadowood Napa Valley Rehabilitation Project
Use Permit Modification Application No. P21-00211-MOD
900 Meadowood Lane, St. Helena
APN's #025-080-032, -033, -034, -035, and -036**

This Permit encompasses and shall be limited to the project commonly known as the Meadowood Resort, located at 900 Meadowood Lane, St. Helena. Part I encompasses the Project Scope and general conditions pertaining to statutory and local code references, project monitoring and the process for any future changes or activities. Part II encompasses the ongoing conditions relevant to the operation of the project. Part III encompasses the conditions relevant to construction and the prerequisites for a Final Certificate of Occupancy. It is the responsibility of the permittee to communicate the requirements of these conditions and mitigations (if any) to all designers, contractors, employees, and the general public to ensure compliance is achieved.

Where conditions are not applicable or relevant to this project, they shall be noted as "Reserved" and, therefore, have been removed.

When modifying a legally established entitlement related to this project, these conditions are not intended to be retroactive or to have any effect on existing vested rights except where specifically indicated.

PART I

1.0 PROJECT SCOPE

This Permit encompasses and modifies, in relevant part, the terms of Use Permit Nos. U-51-61, U-208081, P12-00286, and subsequent modifications, and shall be limited to:

- 1.1 Approval of a Use Permit Minor Modification to Meadowood Napa Valley previous approvals, consisting of the rebuilding and rehabilitation of Meadowood's structures and facilities, including increasing the overall floor area from 154,000 sf to 192,500 sf, as follows:
 - a. approximately 33,240 sf of floor area for food and beverage facilities;
 - b. approximately 40,025 sf of floor area for resort amenities;
 - c. approximately 30,260 sf of floor area for administrative and back-of-house facilities;
 - d. approximately 88,975 sf of floor area for lodging with no increase to the number of the previously approved 106 guest bedrooms or keys;
 - e. parking for 350 vehicles;
 - f. internal access roads;
 - g. landscaping; and,
 - h. associated infrastructure.

The improvements shall be designed in substantial conformance with the submitted development plan, site plan, elevation drawings, and other submittal materials and shall comply with all requirements of the Napa County Code (the County Code). It is the responsibility of the permittee to communicate the requirements of these conditions and mitigations (if any) to all designers, contractors, employees, and the general public to

ensure compliance is achieved. Any expansion of or change in use or alternative locations for fire suppression or other types of water tanks shall be approved in accordance with the County Code and may be subject to the permit modification process.

2.0 STATUTORY AND CODE SECTION REFERENCES

All references to statutes and code sections shall refer to their successor as those sections or statutes may be subsequently amended from time to time.

3.0 MONITORING COSTS

All Staff costs associated with monitoring compliance with these conditions, previous permit conditions, and project revisions shall be borne by the permittee and/or property owner. Costs associated with conditions of approval and mitigation measures that require monitoring, including investigation of complaints, other than those costs related to investigation of complaints of non-compliance that are determined to be unfounded, shall be charged to the property owner or permittee. Costs shall be as established by resolution of the Board of Supervisors in accordance with the hourly consulting rate established at the time of the monitoring and shall include maintenance of a \$500 deposit for construction compliance monitoring that shall be retained until issuance of a Final Certificate of Occupancy. Violations of conditions of approval or mitigation measures caused by the permittee's contractors, employees, and/or guests are the responsibility of the permittee.

The Planning Commission may implement an audit program if compliance deficiencies are noted. If evidence of a compliance deficiency is found to exist by the Planning Commission at some time in the future, the Planning Commission may institute the program at the permittee's expense (including requiring a deposit of funds in an amount determined by the Commission) as needed until compliance assurance is achieved. The Planning Commission may also use the data, if so warranted, to commence revocation proceedings in accordance with the County Code.

PART II

4.0 OPERATIONAL CHARACTERISTICS OF THE PROJECT

Permittee shall comply with the following during operation of the project:

4.1 GROUND WATER MANAGEMENT – WELLS [RESERVED]

4.2 AMPLIFIED MUSIC [RESERVED]

4.3 TRAFFIC

To the maximum extent feasible, scheduling of reoccurring vehicle trips to and from the site for employees and deliveries shall not occur during peak travel times 4:00 PM to 6:00 PM weekdays; 1:00 PM to 3:00 PM Saturdays and Sundays. All road improvements on private property required per Engineering Services shall be maintained in good working condition and in accordance with the Napa County Roads and Streets Standards.

4.4 PARKING [RESERVED]

4.5 BUILDING DIVISION – USE OR OCCUPANCY CHANGES

Please contact the Building Division with any questions regarding the following:

In accordance with the California Building Code (CBC), no change shall be made in the use or occupancy of an existing building unless the building is made to comply with requirements of the current CBC as for a new building.

4.6 FIRE DEPARTMENT – TEMPORARY STRUCTURES **[RESERVED]**

4.7 NAPA COUNTY MOSQUITO ABATEMENT PROGRAM **[RESERVED]**

4.8 GENERAL PROPERTY MAINTENANCE – LIGHTING, LANDSCAPING, PAINTING, OUTDOOR EQUIPMENT STORAGE, MECHANICAL EQUIPMENT, AND TRASH ENCLOSURE AREAS

- a. All lighting shall be permanently maintained in accordance with the lighting and building plans approved by the County.
- b. All landscaping shall be permanently maintained in accordance with the landscaping approved by the County.
- c. All outdoor screening, storage, mechanical equipment and utility structures shall be permanently maintained in accordance with the landscaping and building plans approved by the County. No stored items shall exceed the height of the screening. Exterior equipment shall be maintained so as to not create a noise disturbance or exceed noise thresholds in the County Code.
- d. The colors used for the roof, exterior walls and built landscaping features of the project shall be limited to earth tones that will blend the facility into the colors of the surrounding site specific vegetation. The permittee shall obtain the written approval of the Planning Division prior to any change in paint color that differs from the approved building permit. Highly reflective surfaces are prohibited.
- e. Designated trash enclosure areas shall be made available and properly maintained for intended use.

4.9 NO TEMPORARY SIGNS

Temporary off-site signage, such as “A-Frame” signs are prohibited.

4.10 COMPLIANCE WITH OTHER DEPARTMENTS AND AGENCIES - OPERATIONAL CONDITIONS

The attached project conditions of approval include all of the following County Divisions, Departments and Agencies’ requirements. Without limiting the force of those other requirements which may be applicable, the following are incorporated by reference as enumerated herein:

- a. Environmental Health Division operational conditions as stated in their Memorandum dated August 8, 2022.

- b. Fire Department operational conditions as stated in their Inter-Office Memo dated August 4, 2022.

The determination as to whether or not the permittee has substantially complied with the requirements of other County Divisions, Departments and Agencies shall be determined by those County Divisions, Departments or Agencies. The inability to substantially comply with the requirements of other County Divisions, Departments and Agencies may result in the need to modify this permit.

4.11 OPERATIONAL MITIGATION MEASURES **[RESERVED]**

4.12 OTHER CONDITIONS APPLICABLE TO THE OPERATIONAL ASPECTS OF THE PROJECT

The permittee shall comply with the previous conditions of approval for the project. To the extent there is a conflict between a previous condition of approval and these conditions, the more stringent condition shall control.

4.13 PREVIOUS CONDITIONS **[RESERVED]**

PART III

5.0 PREREQUISITE FOR ISSUANCE OF PERMITS

5.1 PAYMENT OF FEES

No building, grading or sewage disposal permits shall be issued or other permits authorized until all accrued planning permit processing fees have been paid in full. This includes all fees associated with plan check and building inspections, associated development impact fees established by County Ordinance or Resolution, and the Napa County Affordable Housing Mitigation Fee in accordance with County Code.

6.0 GRADING/DEMOLITION/ENVIRONMENTAL/BUILDING PERMIT/OTHER PERMIT PREREQUISITES

Permittee shall comply with the following with the submittal of a grading, demolition environmental, building and/or other applicable permit applications:

6.1 COMPLIANCE WITH OTHER DEPARTMENTS AND AGENCIES - PLAN REVIEW, CONSTRUCTION AND PREOCCUPANCY CONDITIONS

The attached project conditions of approval include all of the following County Divisions, Departments and Agencies' requirements. The permittee shall comply with all applicable building codes, zoning standards, and requirements of County Divisions, Departments and Agencies at the time of submittal and may be subject to change. Without limiting the force of those other requirements which may be applicable, the following are incorporated by reference as enumerated herein:

- a. Environmental Health Division plan review/construction/preoccupancy conditions as stated in their Memorandum dated August 8, 2022.

- c. Fire Department plan review/construction/preoccupancy conditions as stated in their Inter-Office Memo dated August 4, 2022.

The determination as to whether or not the permittee has substantially complied with the requirements of other County Divisions, Departments and Agencies shall be determined by those County Divisions, Departments or Agencies. The inability to substantially comply with the requirements of other County Divisions, Departments and Agencies may result in the need to modify the permit.

6.2 BUILDING DIVISION – GENERAL CONDITIONS

Please contact the Building Division with any questions regarding the following:

- a. A building permit shall be obtained for all construction occurring on the site not otherwise exempt by the CBC or any State or local amendment adopted thereto
- b. If there are any existing structures and/or buildings on the property that will need to be removed to accommodate construction activities, a separate demolition permit shall be required from the Building Division prior to removal. The permittee shall provide a “J” number from the Bay Area Air Quality Management District (BAAQMD) at the time the permittee applies for a demolition permit if applicable.
- c. All areas of newly designed and newly constructed buildings, facilities and or site improvements must comply with the CBC accessibility requirements, as well as, American with Disabilities Act requirements when applicable. When alterations or additions are made to existing buildings or facilities, an accessible path of travel to the specific area of alteration or addition shall be provided as required per the CBC.

6.3 LIGHTING – PLAN SUBMITTAL

- a. Two (2) copies of a detailed lighting plan showing the location and specifications for all lighting fixtures to be installed on the property shall be submitted for Planning Division review and approval. All lighting shall comply with the CBC.
- b. All exterior lighting, including landscape lighting, shall be shielded and directed downward; located as low to the ground as possible; the minimum necessary for security, safety, or operations; on timers; and shall incorporate the use of motion detection sensors to the greatest extent practical. All lighting shall be shielded or placed such that it does not shine directly on adjacent properties or impact vehicles on adjacent streets. No flood-lighting or sodium lighting of the building is permitted, including architectural highlighting and spotting. Low-level lighting shall be utilized in parking areas as opposed to elevated high-intensity light standards.

6.4 LANDSCAPING – PLAN SUBMITTAL

- a. Two (2) copies of a detailed final landscaping and irrigation plan, including parking details, shall be submitted with the building permit application package for the Planning Division’s review and approval prior

to the issuance of any building permit associated with this permit. The plan shall be prepared pursuant to the Water Efficient Landscape Ordinance (Chapter 18.118 of the County Code) requirements in effect at the time of building permit application submittal, as applicable, and shall indicate the names and locations of all plant materials to be used along with their method of maintenance.

- b. Plant materials shall be purchased locally when practical, and, to the greatest extent possible, the plant materials shall be the same native plants found in Napa County. The Agricultural Commissioner's office shall be notified of all impending deliveries of live plants with points of origin outside of Napa County.
- c. No trees greater than 6" diameter at breast height shall be removed, except for those identified on the submitted site plan. Any Oak trees removed as a result of the project shall be replaced at a 2:1 ratio and shown on the landscaping plans for the Planning Division's review and approval. Trees to be retained shall be protected during construction by fencing securely installed at the outer most dripline of the tree or trees. Such fencing shall be maintained throughout the duration of the work undertaken in connection with project development/construction. In no case shall construction material, debris or vehicles be stored in the fenced tree protection area.
- d. Evergreen screening shall be installed between the industrial portions of the operation (e.g., tanks, crushing area, parking area, etc.) and any off-site residence from which these areas can be viewed.
- e. All landscaped areas and sidewalks shall be separated from parking and drive aisle areas by a minimum 6-inch raised concrete curb.

6.5 COLORS

The colors used for the roof, exterior walls and built landscaping features of the project shall be limited to earth tones that will blend the facility into the colors of the surrounding site specific vegetation. The permittee shall obtain the written approval of the Planning Division in conjunction with building permit review and/or prior to painting the building. Highly reflective surfaces are prohibited.

6.6 OUTDOOR STORAGE/SCREENING/UTILITIES

- a. Details of outdoor storage areas and structures shall be included on the building and landscape plans. All outdoor storage of equipment shall be screened from the view of residences of adjacent properties by a visual barrier consisting of fencing or dense landscaping. No stored item shall exceed the height of the screening. Water and fuel tanks, and similar structures, shall be screened to the extent practical so as to not be visible from public roads and adjacent parcels.
- b. New utility lines required for this project that are visible from any designated scenic transportation route (see Community Character Element of the General Plan and the County Code) shall be placed underground or be made virtually invisible from the subject roadway.

6.7 MECHANICAL EQUIPMENT

- a. Roof mounted equipment shall be screened by a parapet wall of equal or greater height than the highest piece of roof mounted equipment or vent. Equipment may be screened by a separate roof screen that is architecturally integrated with the building if screening by a parapet wall is not feasible or is architecturally undesirable. When separate roof screens are used, roof equipment should be organized into major groups screening a smaller number of units rather than multiple areas. The PBES Director may approve exceptions for solar equipment. All screening is subject to review and approval by the PBES Director. Any skylights shall be subject to review and approval by the PBES Director prior to the issuance of building permits.
- b. The term "equipment" includes roof mounted equipment or vents, electrical equipment, gas meter, communication antennas, irrigation valves, storage tanks, or other mechanical equipment. The manner of screening shall be as follows: Communications equipment, including microwave equipment, may remain unscreened if visually integrated with the building design through color, location, and construction; all building mounted equipment, including but not limited to louvers, pipes, overhead doors or service doors, access ladders, downspouts, conduit, and electrical/service boxes, shall be painted consistent with the color scheme of the building.
- c. Ground mounted equipment shall be screened by walls or landscaping to the satisfaction of the PBES Director.
- d. Exterior equipment shall be located, enclosed or muffled so as not to exceed noise thresholds in the County Code.

6.8 TRASH ENCLOSURES

Adequate area must be provided for collection and loading of garbage and recyclables generated by the project. The applicant must work with the franchised garbage hauler for the service area in which they are located, in order to determine the area and the pedestrian and vehicle access needed for the collection site. The garbage and recycling enclosure shall meet the minimum enclosure requirements established by staff and the franchised hauler, which shall be included in the building permit submittal.

6.9 ADDRESSING

All project site addresses shall be determined by the PBES Director, and be reviewed and approved by the United States Post Office. The PBES Director reserves the right to issue or re-issue an appropriate situs address at the time of issuance of any building permit to ensure proper identification and sequencing of numbers. For multi-tenant or multiple structure projects, this includes building permits for later building modifications or tenant improvements.

6.10 HISTORIC RESOURCES **[RESERVED]**

6.11 DEMOLITION ACTIVITIES **[RESERVED]**

- 6.12 VIEWSHED – EXECUTION OF USE RESTRICTION **[RESERVED]**
- 6.13 PERMIT PREREQUISITE MITIGATION MEASURES **[RESERVED]**
- 6.14 PARCEL CHANGE REQUIREMENTS **[RESERVED]**
- 6.15 FINAL MAPS **[RESERVED]**
- 6.16 OTHER CONDITIONS APPLICABLE TO THE PROJECT PERMITTING PROCESS **[RESERVED]**

7.0 PROJECT CONSTRUCTION

Permittee shall comply with the following during project construction:

7.1 SITE IMPROVEMENT

Please contact Engineering Services with any questions regarding the following:

a. GRADING & SPOILS

All grading and spoils generated by construction of the project facilities shall be managed per Engineering Services direction. Alternative locations for spoils are permitted, subject to review and approval by the PBES Director, when such alternative locations do not change the overall concept, and do not conflict with any environmental mitigation measures or conditions of approval.

b. DUST CONTROL

Water and/or dust palliatives shall be applied in sufficient quantities during grading and other ground disturbing activities on-site to minimize the amount of dust produced. Outdoor construction activities shall not occur when average wind speeds exceed 20 mph.

c. AIR QUALITY

During all construction activities the permittee shall comply with the most current version of BAAQMD Basic Construction Best Management Practices including but not limited to the following, as applicable:

1. Post a publicly visible sign with the telephone number and person to contact at the lead agency regarding dust complaints. The BAAQMD's phone number shall also be visible.
2. Water all exposed surfaces (e.g., parking areas, staging areas, soil piles, grading areas, and unpaved access roads) two times per day.
3. Cover all haul trucks transporting soil, sand, or other loose material off-site.
4. Remove all visible mud or dirt tracked onto adjacent public roads by using wet power vacuum street sweepers at least once per day. The use of dry power sweeping is prohibited.

5. All vehicle speeds on unpaved roads shall be limited to 15 mph.
6. All roadways, driveways, and sidewalks to be paved shall be completed as soon as possible. Building pads shall be laid as soon as possible after grading unless seeding or soil binders are used.
7. Idling times shall be minimized either by shutting off equipment when not in use or reducing the maximum idling time to five (5) minutes (as required State Regulations). Clear signage shall be provided for construction workers at all access points.
8. All construction equipment shall be maintained and properly tuned in accordance with manufacturer's specifications. All equipment shall be checked by a certified visible emissions evaluator. Any portable engines greater than 50 horsepower or associated equipment operated within the BAAQMD's jurisdiction shall have either a California Air Resources Board (ARB) registration Portable Equipment Registration Program (PERP) or a BAAQMD permit. For general information regarding the certified visible emissions evaluator or the registration program, visit the ARB FAQ http://www.arb.ca.gov/portable/perp/perpfaq_04-16-15.pdf or the PERP website <http://www.arb.ca.gov/portable/portable.htm>.

d. **STORM WATER CONTROL**

The permittee shall comply with all construction and post-construction storm water pollution prevention protocols as required by the County Engineering Services Division, and the State Regional Water Quality Control Board.

7.2 ARCHEOLOGICAL FINDING

In the event that archeological artifacts or human remains are discovered during construction, work shall cease in a 50-foot radius surrounding the area of discovery. The permittee shall contact the PBES Department for further guidance, which will likely include the requirement for the permittee to hire a qualified professional to analyze the artifacts encountered and to determine if additional measures are required.

If human remains are encountered during project development, all work in the vicinity must be halted, and the Napa County Coroner informed, so that the Coroner can determine if an investigation of the cause of death is required, and if the remains are of Native American origin. If the remains are of Native American origin, the permittee shall comply with the requirements of Public Resources Code Section 5097.98.

7.3 CONSTRUCTION NOISE

Construction noise shall be minimized to the greatest extent practical and feasible under State and local safety laws, consistent with construction noise levels permitted by the General Plan Community Character Element and the County Noise Ordinance. Construction equipment muffling and hours of

operation shall be in compliance with the County Code. Equipment shall be shut down when not in use. Construction equipment shall be staged, loaded, and unloaded on the project site, if at all practicable. If project terrain or access road conditions require construction equipment to be staged, loaded, or unloaded off the project site (such as on a neighboring road or at the base of a hill), such activities only shall occur daily between the hours of 8:00 AM to 5:00 PM.

7.4 CONSTRUCTION MITIGATION MEASURES **[RESERVED]**

7.5 OTHER CONSTRUCTION CONDITIONS APPLICABLE TO THE PROJECT PROPOSAL **[RESERVED]**

8.0 TEMPORARY CERTIFICATE OF OCCUPANCY – PREREQUISITES

A Temporary Certificate of Occupancy (TCO) may be granted pursuant to the County Code to allow specific limited use of the project recreational vehicle units prior to completion of all project improvements. Permittee shall comply with the following before a TCO is granted:

8.1 TEMPORARY OCCUPANCY

All life and safety conditions shall be addressed prior to issuance of a TCO by the County Building Official. TCOs shall not be used for the occupancy of hospitality buildings and shall not exceed the maximum time allowed by the County Code which is 180 days. In special circumstances, Departments and/or Agencies with jurisdiction over the project are authorized as part of the TCO process to require a security deposit or other financial instrument to guarantee completion of unfinished improvements.

9.0 FINAL CERTIFICATE OF OCCUPANCY – PREREQUISITES

Permittee shall comply with the following before a Final Certificate of Occupancy is granted by the County Building Official, which upon granting, authorizes all use permit activities to commence:

9.1 FINAL OCCUPANCY

All project improvements, including compliance with applicable codes, conditions, and requirements of all Departments and Agencies with jurisdiction over the project, shall be completed.

9.2 SIGNS

Detailed plans, including elevations, materials, color, and lighting for any project identification or directional signs shall be submitted to the Department for administrative review and approval prior to installation. Administrative review and approval is not required if the signage to be installed is consistent with signage plans submitted, reviewed and approved as part of this permit approval. All signs shall meet the design standards as set forth in the County Code. Any off-site signs allowed shall be in conformance with the County Code.

9.3 GATE/ENTRY STRUCTURES

Any gate installed at the project entrance shall be reviewed by the PBES Department and the Fire Department to assure that the design allows large

vehicles, such as motorhomes, to turn around if the gate is closed without backing into the public roadway, and that fire suppression access is available at all times. If the gate is part of an entry structure an additional permit shall be required pursuant to the County Code and in accordance with the Napa County Roads and Street Standards. A separate entry structure permit is not required if the entry structure is consistent with entry structure plans submitted, reviewed, and approved as part of this permit approval.

9.4 LANDSCAPING

Landscaping shall be installed in accordance with the approved landscape plan.

9.5 ROAD OR TRAFFIC IMPROVEMENT REQUIREMENTS **[RESERVED]**

9.6 DEMOLITION ACTIVITIES **[RESERVED]**

9.7 GRADING SPOILS

All spoils piles shall be removed in accordance with the approved grading permit and/or building permit.

9.8 MITIGATION MEASURES APPLICABLE PRIOR TO ISSUANCE OF A FINAL CERTIFICATE OF OCCUPANCY **[RESERVED]**

9.9 OTHER CONDITIONS APPLICABLE PRIOR TO ISSUANCE OF A FINAL CERTIFICATE OF OCCUPANCY

All project improvements and conditions of approval, including compliance with prior conditions of approval in Exhibit B, shall be completed prior to issuance of a final certificate of occupancy.



A Tradition of Stewardship
A Commitment to Service

Planning, Building & Environmental Services

1195 Third Street, Suite 210
Napa, CA 94559
www.countyofnapa.org

David Morrison
Director

MEMORANDUM

To: Sean Trippi, Project Planner	From: Kim Withrow, Environmental Health Supervisor <i>KDW</i>
Date: August 8, 2022	Re: Meadowood Development Plan – Glass Fire Rehabilitation Project APN: 025-080-(032-036) Project #: P21-00211

This Division has reviewed a development agreement for the rehabilitation of Meadowood Resort damaged by the 2020 Glass Fire as described and depicted in application materials. This Division has no objection to approval of the application with the following conditions of approval:

Prior to issuance of building permits:

1. The applicant shall secure (or update) a discharge requirement or waiver of same, from the Regional Water Quality Control Board for the waste water system improvements.
2. Plans for the proposed sanitary waste treatment and reuse system shall be submitted for review. No building clearance (or issuance of a building permit) for any structure that generates wastewater to be disposed of by this system will be approved until such plans are approved by this Division.
3. A permit to construct the sanitary waste water treatment system and must be secured from this Division prior to approval of a building clearance (or issuance of a building permit) for any structure that generates wastewater to be disposed of by this system.
4. Complete plans and specifications for the food preparation, service area(s), storage area(s) and the employee restrooms must be submitted for review and approval by this Division prior to issuance of any building permits for said areas. An annual food permit will be required.
5. Complete plans for the swimming pool and/or spa must be submitted to this Division for review and approval prior to approval of building permits. An annual pool permit will be required.

6. Adequate area must be provided for collection of recyclables. The applicant must work with the franchised garbage hauler for the service area in which they are located, in order to determine the area and the access needed for the collection site. The garbage and recycling enclosure must meet the enclosure requirements provided during use permit process and be included on the building permit submittal. The designated area shall remain available and be properly maintained for its intended use.
7. The parcel must continue to be served by City of St. Helena for water service.

Prior to granting final occupancy:

8. During the construction, demolition, or renovation period of the project the applicant must use the franchised garbage hauler for the service area in which they are located for all wastes generated during project development, unless applicant transports their own waste. If the applicant transports their own waste, they must use the appropriate landfill or solid waste transfer station for the service area in which the project is located.
9. Annual food and pool permits must be secured prior to granting final occupancy.

Upon final occupancy and thereafter:

10. Within 30 (thirty) days of initiation of the use or change of tenants, an updated Hazardous Materials Business shall be submitted to <http://cers.calepa.ca.gov/> and approved by this Division.
11. All solid waste shall be stored and disposed of in a manner to prevent nuisances or health threats from insects, vectors and odors.



A Tradition of Stewardship
A Commitment to Service

Napa County Fire Department
Fire Marshal's Office
Hall of Justice, 2nd Floor
1125 3rd Street
Napa, CA 94559

Office: (707) 299-1464

James Bales
Fire Marshal

MEMORANDUM

TO:	Planning Department	DATE:	8/4/2022
FROM:	Jason Downs, Deputy Fire Marshal	PERMIT #	P21-00211
SUBJECT:	Meadowood Resort Development Agreement	APN:	025-080-032-000

The Napa County Fire Marshal's Office has reviewed the submittal package for the above-proposed project. The Fire Marshal approves the project as submitted with the following conditions of approval:

1. All construction and use of the facility shall comply with all applicable standards, regulations, codes, and ordinances at the time of Building Permit issuance.
2. Beneficial occupancy will not be granted until all fire department fire and life safety items have been installed, tested, and finalized.
3. Where conditions listed in 2019 California Fire Code Section 105.7 are proposed, separate permits will be required prior to Building Permit issuance for:
 1. Automatic fire-extinguishing systems
 2. Emergency responder radio coverage systems
 3. Fire alarm detection systems and related equipment
 4. Fire pumps and related equipment
 5. Gates and barricades across fire apparatus access roads
 6. Private fire hydrants
 7. Smoke control or smoke exhaust systems
 8. Solar photovoltaic power systems
 9. Special event structure
 10. Standpipe systems
 11. Temporary membrane structures
 12. Tents
4. Where conditions listed in the 2019 California Fire Code, Chapter 4, are proposed (indoors or outdoors) an Emergency Response Plan is required for: **Group A** occupancies (with an occupant load greater than 2000), **Group B** occupancies (with an occupant load greater than 500 or more than 100 above or below the lowest level of exit discharge), **Group M** occupancies (with an occupant load greater than 500 or more than 100 above or below the lowest level of exit discharge).



A Tradition of Stewardship
A Commitment to Service

Napa County Fire Department
Fire Marshal's Office
Hall of Justice, 2nd Floor
1125 3rd Street
Napa, CA 94559

Office: (707) 299-1464

James Bales
Fire Marshal

MEMORANDUM

5. All buildings, facilities, and developments shall be accessible to fire department apparatus by way of approved access roadways and/or driveways. The fire access road shall comply with the requirements of the Napa County Road & Street Standards
6. Access roads shall be designed and maintained to support the imposed loads of fire apparatus and shall be surfaced to provide all-weather driving capabilities. Provide an engineered analysis of the proposed roadway noting its ability to support apparatus weighing 75,000 lbs.
7. Provide fire department access roads within 150 feet of any exterior portion of the buildings as measured by an approved route around the exterior of the building or facility.
8. Roadways shall be a minimum of 20 feet in width with a 2-foot shoulder and 15-foot vertical clearance.
9. Turnouts shall be a minimum of 12 feet in width, 30 feet in length, and a 25-foot taper on each end.
10. Turnarounds are required on driveways and dead-end roadways.
11. Grades for all roadways and driveways shall not exceed 16 percent.
12. Roadway radius shall not have an inside radius of fewer than 50 feet. An additional surface width of 4 feet shall be added to curves of 50-100 feet radius and 2 feet to curves of 100-200 feet radius.
13. Gates for driveways and/or roadways shall comply with the California Fire Code, section 503.5, and the Napa County Road & Street Standards and CA Fire Safe Regulations for projects within SRA.
14. Commercial - Water storage (for buildings not served by a public water system) and fire flow calculations shall be provided by a Certified State Licensed Civil Engineer, C-16 licensed contractor, or registered engineer indicating compliance with California Fire Code Appendix B and the Napa County Municipal Code.
15. Commercial - Approved steamer hydrants shall be installed within 250 feet of any exterior portion of the building as measured along vehicular access roads. Private fire service mains shall be installed, tested, and maintained per NFPA 24.



A Tradition of Stewardship
A Commitment to Service

Napa County Fire Department
Fire Marshal's Office
Hall of Justice, 2nd Floor
1125 3rd Street
Napa, CA 94559

Office: (707) 299-1464

James Bales
Fire Marshal

MEMORANDUM

16. Commercial - Fire Department Connections (FDC) for automatic sprinkler systems shall be located fully visible and recognizable from the street or fire apparatus access roads. FDC shall be located within 50 feet of an approved fire hydrant.
17. Commercial - The minimum main size of all fire hydrants shall be 6 inches in diameter. Piping shall be installed with C-900 class 200 piping or ductile iron or equivalent per NFPA 24 for the installation of Underground Fire Protection Mains
18. An automatic fire sprinkler system shall be installed in accordance with provisions set forth in the California Fire Code as amended by the County of Napa and the applicable National Fire Protection Association Standard. Automatic fire sprinkler systems shall be designed by a fire protection engineer or C-16 licensed contractor.
19. All buildings shall comply with California Fire Code, Chapter 10 Means of Egress Requirements. Including but not limited to; exit signs, exit doors, exit hardware, and exit illumination.
20. Provide 100 feet of defensible space around all structures.
21. Provide 10 feet of defensible space for fire hazard reduction on both sides of all roadways of the facility.
22. Emergency responder radio coverage in new buildings. All new buildings shall have approved radio coverage for emergency responders within the building based upon the existing coverage levels of the public safety communication systems of the jurisdiction at the exterior of the building.

Please note that the comments noted above are based on a Fire Marshal review only. There may be additional comments or information requested from other County Departments or Divisions reviewing this application submittal package. Napa County Fire Marshal's Office Development Guidelines can be found @ www.countyofnapa.org/firemarshal. Should you have any questions for me, please contact me at (707)299-1467 or email at jason.downs@countyofnapa.org